

**Project 1: Removing the notice board at Stocks Green and replace with 2 new boards**

**Labour and materials included in the offer price is as follow ;**

- Demolition /clearance of existing notice board and posts including concrete
- Disposal of all the materials from demolition
- Dig out 4 post holes to 600 mm depth.
- Concrete in /fit 4 pcs new posts-top of post to be @ 1,8 m.(same as ex,notice board)
- Fix 2 new notice boards to the posts – maintenance gap 120 mm between boards.
- The boards to be sitting on a horizontal support timber, running across the 4 posts.  
The support timber to be 45 x 100 mm planed oak to match the other parts .  
The top of boards to be fixed with steel L-brackets one each corner **internally**.  
The lockable notice board to be positioned to the right.
- Clearance of site after work completed.

- 
- **Client to supply the 4 posts and 2 notice boards.**
  - **Contractor to supply rest of the materials .**

**Offer price for material and labour costs : £ 410,00**

**No VAT to be added on the prices.**

---

**Terms of payment :** to be invoiced at the date of work completed.

Invoice to be paid within 7 days .

**Project 2: Work Playing Fields , Common Land. Ref: Safety Inspection Report 27.09.2023**

**Labour and materials included in the offer price is as follow ;**

- **Fencing A1:** Clean up and replace missing parts. *Contractor: Labour & materials*
- **Gates A3:** Rebuild gate +adjust, add new rubber buffer. *Contractor: Labour & materials*
- **Gate A4:** Maintenance,remove mesh,replace ruten slats,parts. *Contractor: Labour & materials*
- **Rocker horse P2:** Replace with new, *Client to supply horse- Contractor: Labour & concrete*
- **Square Climber frame P7-P9:** Tighten/adjust parts & Replace missing parts.  
- *Parts to be supplied by client.*

Fit galvanized post protectors to bottom of all 12 structural posts, the protectors to go 70 mm below ground level and 170 mm above the ground = up the post.

*Contractor to supply protectors and Labour*

- **Agility ladder P10 :** Fit post protectors to all 4 posts, *as above. Contractor: Labour & material*
- **Goal posts 5-A-side P11:** Descale and paint white, Lead free quality Hamerite paint  
*Contractor: Labour and paints.*
  - **Goal posts Football full size P12-13:** Descale to good base and paint with lead free quality hamerite paint.The bad bits to be pre-coated with red oxide base coat  
*Contractor: Labour and paints.*

---

**Offer price for material and labour costs : £ 1 535,00**

**No VAT to be added on the prices.**

**Terms of payment :** to be invoiced at the date of work completed.

Invoice to be paid within 7 days .