

Playing Field fencing – Phase 2 quote

Client :

Walberswick Parish Council

Walberswick

08.04.2024

Project : *Rebuild the agricultural fencing at the common land joining the Playing Fields.*

*This quote is for **Stage 2** : from the emergency steel gates to the playing fields at “springy”
= to meet up with - Stage 1 Fencing.*

The length of this fencing (included in this quote) is 310 meters. = 40 % longer than Stage 1.

- *Detach the existing fence from the posts and leave , ready to be refitted to new posts.*
- *Remove all the rotten/bad , existing 100 mm posts and the 150 mm straining posts & the strainers.*
- *Drill holes and install 42 pcs, 100 mm kiln dried machined round treated posts – 30 new posts & 12 reclaimed from Stage 1 (as agreed).*
- *Drill holes & install 14 pcs new 150 mm kiln dried round treated straining posts*
- *Install 7 pcs – new 150 mm horizontal Strainers*
- *Refit the fence to the new posts and, add 2,5 mm galvanized diagonal strainers*
- *Fit an additional 2,5mm galvanized top wire to areas missing one.*
- *Tie the existing gate posts to the new straining posts with timber braces*

Labour and materials included in the offer price are as follow:

- *Supply and fit all the materials as listed in this quote.*
- *Clear all the builders rubbish after work completed, and disposal of old rotten timber*
- *Transport all needed material – materials to be stored at safe store until fitting*

Material costs : £ 1 720,00

Labour costs : £ 2 080,00

No VAT to be added.

Quoted prices : Material part valid 14 days & Labour part valid 30 days.

Terms of payment :

Material costs to be invoiced and paid on the date of order.

Outstanding balance = Labour costs to be invoiced and paid when work completed.

Fully insured .