

## Quotation for Playing Ground fencing – Phase 1

**Project :** *Rebuild the agricultural fencing at the common land joining the Playing Fields.*

*This quote is for **Stage 1**- from the playing fields to the emergency steel gates opposite side.*

*The length of this fencing (included in this quote) is 220 meters.*

*Attached is 2 photos : Start point & Finish point.*

- *Detach the existing fence from the posts and leave , ready to be refitted to new posts.*
- *Remove the existing 100 mm posts and the 150 mm straining posts & the strainers*
- *Drill holes and install 52 pcs new 100 mm kiln dried machined round treated posts*
- *Drill holes & install 20 pcs new 150 mm kiln dried round treated straining posts*
- *Install 12 pcs – new 150 mm horizontal Strainers*
- *Refit the fence to the new posts and, add 2,5 mm galvanized diagonal strainers*
- *Tie the existing gate posts to the new straining posts with timber braces*

**Labour and materials included in the offer price are as follow:**

- Supply and fit all the materials as listed in this quote.
- Clear all the builders rubbish after work completed, and disposal of old rotten timber
- Transport all needed material – materials to be stored at safe store until fitting
- The removed existing posts & strainers which are OK, to be kept and used for Stage 2

**Material costs :** £ 2 144,00

**Labour costs :** £ 1 630,00

**No VAT to be added.**

**Quote: Material part valid 7 days & Labour part valid 21 days.**

**Terms of payment :**

Material costs to be invoiced and paid on the date of order.

Outstanding balance to be invoiced and paid when work completed.